

HAMILTON UNIFIED SCHOOL DISTRICT

HAMILTON ELEMENTARY SCHOOL PAVING & DRAINAGE PROJECT

BID ADDENDUM NO. 1

MARCH 27, 2015

Bid Walk Q & As:

- The Civil Engineer has determined that “The area of disturbance is less than one acre, consequently, no SWPPP is required”
- The project will not require DSA certification.
- As noted in the Bid Notice, Bid Documents and Contract, the appropriate Labor Code sections dealing with Prevailing Wages, Labor Compliance Programs and Apprenticeship Requirements will be enforced.
- A Reroofing/HVAC Replacement project on the Administration Building will be scheduled concurrently with this project; it will be the Contractor’s responsibility to appropriately schedule his work in order to complete this project within the required timeline. No other District-authorized activities or programs will be conducted on the school site during the required project timeline (General Conditions-Section 5.C.).
- There are existing utilities in the area of work. The drawings have been updated with record information, attached.
- Existing utilities are to be located (per Section 02200) and potholed as noted on the plans prior to the start of demolition, excavation and/or trenching.
- The extent of sod replacement is identified on the plans, attached.
- The downspout connection at the column has been modified, see plans attached.
- Grading has been modified, see attached plans.